No.	Items of work	Unit	Quantity
20	Providing teakwood screen with doors at lavatory compartments as per design of Ul. C. enclosure at the Legislative Council Hall bath rooms complete with nickel plated spring hinges to doors yale locks etc., with white enamelled painting inside and polishing outside.	S.ft.	250
21	Providing and laying and jointing $\frac{3}{4}$" galvanized pipes including cost of fittings cutting and threading and grooving walls or floor and redoing.	R.ft.	200
22	Fixing $1\frac{1}{2}$" lead pipes with wiped solder joints to lavatory waste ...	No.	4
23	Providing $\frac{1}{2}$" and $\frac{3}{4}$" lead pipes and fixing with wiped solder joints, etc., complete.	"	16
	Drainage arrangements.		
1	Earthwork excavation for pipe trenches including fitting trenches watering and tamping and removal of surplus earth.	C.yd.	325
2	Laying and jointing stone ware pipes of approved quantity with cement mortar including cost of pipes—		
	(*a*) 4" pipe line	R.ft.	60
	(*b*) 6" pipe line	"	720
3	Constructing square manholes up to 5' depth with earthwork excavation 9" brick walls 9" surki concrete bed construction of inside drains cement plastering and providing and fixing 21" C. I. manhole cover and frame and steps where required.	No.	5

B. R. GARUDACHAR,
Executive Engineer.

KOLAR DIVISION.

Dated 1st August 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division up to 2 P.M., 21st August 1931, for restoring the Breached Byatarayanahalli Devarakere Minor Tank, Regd. No. 193 of Malur Taluk, Kolar District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th June 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and eighty (Rs. 180) only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring the Breached Byatarayanahalli, Devarakere Minor Tank, Regd. No. 193 of Malur Taluk, Kolar District" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of the work both in words and figures.

10. The tenders stating that the work would be executed at a certain percentage in excess or lower than the estimated rates will not be accepted.

Estimate of quantities for restoring the Breached Byatarayanahalli Devarakere Minor Tank Registered No. 193, Malur Taluk, Kolar District.

Sl. No.	Particulars	Unit	Rs. a. p.	Quantity	Cost
	Bund.				
1	Earth work to bund watering and tamping to R. L. 55·00 including lead and lift	C.yd.		5489	
2	Earth work to breach watering and tamping	,,		729	
3	Turfing to bund	S.yd.		3323	
4	Removing and resetting old stone work with new jelly.	C.yd.		258	
5	New stone work with new jelly	,,		595	
6	Fixing new grade stones with figuring, painting complete.	No.		11	
7	Do Index Stones ...	,,		11	
8	Do B. M. Stones ...	,,		2	
9	Do Register No. Stone ...	,,		1	
10	Do Gauge Stone ...	,,		1	
11	Earth work excavation in breach for puddle wall.	C.yd.		28	
12	Puddle wall in good clay ...	,,		124	
13	Jungle clearing and removing Ant-hills ...	Lump	Sum		
	Sluice R. L. 45·00.				
1	Earth work excavation	C.yd.		30	
2	Refilling the same with watering and tamping	,,		30	
3	Surki Concrete	C.ft.		278	
4	Burnt stone slabs 4" to 6" thick ...	S.ft.		182	
5	Burnt brick in surki mortar	C.ft.		302	
6	Plastering with Surki Mortar	Sqr.		5·04	
7	Drilling holes in gibbet cross and orifice ...	Lump	Sum		
8	Providing wooden plug and iron rod 2" Dia.	Lump	Sum		
	Waste weir 50·00.				
1	Earth work excavation for body wall and return.	C.yd.		12	
2	Surki concrete	C.ft.		127	
3	Burnt brick in surki mortar	,,		345	
4	Burnt stone labs	S.ft.		56	
5	Plastering with surki mortar	Sqr.		5·04	
6	Joggle joints	No.		5	

C. T. NARASIMHA IYENGAR,
Executive Engineer.

KADUR DIVISION.

Abstract Notification dated 31st July 1931.

The attention of the public is invited to the notice calling for tenders for constructing Anicut across Byranji halla, published on pages 839 to 841, Part VI of *Mysore Gazette*, dated 6th August 1931. The last date for receiving tenders is 24th August 1931.

L. A. H. WINCKLER,
Executive Engineer.